

SENT VIA EMAIL ONLY

September 30, 2025 (Revised)



Katrina Glynn
Community Development Director
Village of Saranac Lake
39 Main Street, Suite 9
Saranac Lake, NY, 12983
comdev@saranaclakeny.com

Re: Village Beach Site Improvement Project
Lake Colby
Saranac Lake, NY
MJ Proposal No. 2025380 for Engineering and Survey Services

Dear Ms. Glynn:

MJ Engineering, Architecture, Landscape Architecture, and Land Surveying, P.C. (MJ) is pleased to provide the Village of Saranac Lake (Village) with this proposal for professional architectural, engineering, and surveying services for the Village Beach Site Improvement Project (Project). The project will include site improvements at the Village Beach located at Moir Road in Saranac Lake, NY. MJ's project understanding and associated Scope of Services are included below.

PROJECT UNDERSTANDING

Based upon information provided by the Village, MJ understands the following:

- The Village Beach is a free recreational amenity for residents and visitors. It is located within walking and biking distance of the village center and has available on-site parking.
- The existing comfort station building includes restrooms, lifeguard area, and a small storage area. The building is connected to municipal sanitary sewer and water services and has electrical service.
- The Village is currently securing grant funding for the parking lot stormwater improvements separately and is interested in securing grant funding for the new site design.
- The Village is seeking a proposal to address the following site design items:
 - Installation of fencing to separating the play area and parking lot from the swimming area as required by the New York State Department of Health (NYSDOH).
 - Removal of existing comfort station and preparation of the site for construction of a future new comfort station.
 - Construction of ADA compliant paths throughout the site.
 - Comfort station and pavilion building programming study.
 - Development of stormwater improvements to divert water away from the beach and proposed future structures.



21 Corporate Drive
Clifton Park, NY 12065



518.371.0799
mj@mjteam.com
mjteam.com



Fishkill, NY
Levittown, NY
Picatinny, NJ
Melbourne, FL

FOI 26-0415 NFRsp000951



Based upon the above understanding, MJ offers the following Scope of Services for your consideration.

SCOPE OF SERVICES

Task 01: Field Investigations

A. Wetland Delineation and Shoreline Site Screening

1. Review available mapping, including the USGS topographic map, aerial photography, the County Soil Survey, National Wetland Inventory (NWI) maps, and New York State Department of Environmental Conservation (NYSDEC) Freshwater Wetland maps in advance of performing the field work.
2. Regulated wetlands will be field delineated in accordance with the procedures outlined in the 1987 Corps of Engineers Wetland Delineation Manual and the Northcentral and Northeast Regional Supplement. MJ will field locate wetland boundary with numbered flags (tap, pin flags) and will document their location via GPS. MJ will also flag and GPS the Ordinary High Water (OHW) mark of the lake to document the shoreline. A figure that shows the mapped NYSDEC and NWI wetland locations, delineated wetland boundary locations, sampling points, photograph locations, and soil types will be provided.
3. MJ will prepare a Jurisdictional Determination package for the Adirondack Park Agency (APA), New York State Department of Environmental Conservation (NYSDEC) and US Army Corps of Engineers (USACE) confirmation of potential jurisdictional resources. Associated forms and mapping needed for confirmation will be provided. This task includes one site visit with NYSDEC and USACE and minor revisions to documentation of wetland boundary limits.

B. Survey and Mapping

MJ will complete survey and mapping within the project limits as depicted in Figure 1. The tasks to be completed include:

1. Collect topographic data through conventional surveys over the entirety of the area consisting of approximately 2.25 acres. Sufficient data will be collected to generate 1-foot contours.
2. Establish two (2) horizontal control points and two (2) benchmarks to serve as project control.
3. Locate the physical features within the project area including, but not limited to buildings, curbing, sidewalks, utility poles, trees, culverts, manholes, streetlights, curb cuts, and catch basins. Sanitary and storm structures will depict the elevations of the rims along with inverts and the size and directions of pipes. Underground utilities will be shown on the map based upon record information provided by the facility, and data collected during the field survey. Mapping shall be prepared in accordance with ASCE Quality Level C (QLC) Standards.
4. Locate wetland boundary flags.
5. Prepare mapping in AutoCAD Civil 3D 2022 format with 1-foot contours at a scale of 1" = 20' utilizing the data collected in the field and correlating utility records.



C. Geotechnical

1. Advance a maximum of two (2) on-site soil borings.
2. Advance a maximum of two (2) soil test pits and three (3) infiltration tests for stormwater management systems in conformance with the NYSDEC Stormwater Management Design Manual.
3. Perform soil sampling and visual classification of the soil and/or rock samples. Conduct on-site and laboratory testing.
4. Prepare a Geotechnical Report with geotechnical recommendations for stormwater systems and shallow foundations.

D. Hazardous Materials Survey and Testing

1. Perform survey and sampling of materials to be impacted by the proposed demolition of the existing comfort station building. The task will include review of Asbestos-Containing Materials (ACM), Polychlorinated Biphenyls (PCBs), and Lead.
2. Prepare a Limited Hazardous Materials Survey Report summarizing the findings of the survey and testing.

Task 02: Design & Permitting Phase

A. Schematic Design

1. Develop concept drawings to capture the scope of desired site programing, building programming, and infrastructure needs within the project limits bound by the guiderail at the north side of Moir Rd, the west edge of the Village Beach parking lot, and the east shore of Lake Colby. Refer to Figure 1. Concept Design drawings will include two (2) alternative programmatic site plans, and two (2) alternative programmatic comfort station and pavilion floor plans that organize the desired amenities and improvements differently. Meet with the Village following submission of the concept design to review the design options and select one alternative to advance.
2. Provide a Schematic Design submission including 30% level drawings of the selected concept site and comfort station alternative. A construction cost estimate and Basis of Design document will be included in the Schematic Design submission to the Village. The Basis of Design document will capture key decisions and additional information needed to advance the design.

B. Design Development

1. Advance the project plans to approximately 90% development incorporating the Village's comments on the Schematic Design Submission.
2. Develop a Project Manual including Front End and Technical Specifications.
3. Revise the construction cost estimate.
4. Provide a Design Development Phase submission including plans, project manual, construction cost estimate and draft permitting documents for Village review.



C. Wetland and Shoreline Permitting

1. A Jurisdictional Inquiry Form (JIF) will be prepared and submitted to the APA with the delineation report from Task 01 to determine if the APA will take jurisdiction over the project. A site visit will be requested with the APA as part of this submittal.
2. A site visit will be scheduled with APA to review jurisdiction and project permitting. During this field meeting, pre-application discussions will occur based on Schematic Design Plans prepared under Task 02 in advance of the meeting. Meeting notes will be prepared and provided including any changes made to the original delineation to produce final mapping of the delineation. Any additional permits from other regulatory agencies will be discussed during this meeting, including NYSDEC and USACE.
3. If APA determines a permit will be required for the project, a permit application will be prepared and submitted to the APA for project approval. Any additional permitting identified during the project site visit in relation to work in waters will be applied for as needed.

D. Final Construction Documents

1. Following receipt of the comments on the Design Development Phase submission, MJ will make the necessary revisions to produce the Final Construction Document Submission. The submission will include plans and project manual stamped by a Professional Engineer Licensed in the State of New York.
2. Final permitting documents will be provided to the Village for issuance to regulatory agencies.

Task 03: Stormwater Pollution Prevention Plan (SWPPP)

The proposed project is expected to disturb more than one-acre of soil, which requires the preparation of a full Stormwater Pollution Prevention Plan (SWPPP) that includes post-construction stormwater management practices, and water quality and quantity controls pursuant to the New York State Department of Environmental Conservation's (NYSDEC) State Pollutant Discharge Elimination System (SPDES) General Permit GP-0-25-001.

MJ will prepare a stormwater pollution prevention plan (SWPPP) for the proposed construction phase site disturbances, including all necessary post-construction stormwater management practices, and water quality and quantity controls. The report will be developed following the GP-0-25-001 and NYSDEC Stormwater Management Design Manual (July 2024).

ASSUMPTIONS

The following assumptions were made in the development of this proposal:

1. The Village will:
 1. Coordinate and arrange for necessary access provisions to allow MJ field staff and subconsultants access to the site.
 2. Provide MJ's field crews with unfettered access to the site to complete field work during normal business hours (7:30 AM-5:00 PM Monday-Friday) not to exceed 40 hours in a week.
 3. Submit the prepared permit applications to the respective regulatory agencies.



4. Provide record documentation, if available, which includes but is not limited to soil borings, design plans, utility mapping, emergency repair design documents, and inspection reports.
5. Be fully responsible for completing all procedural steps and forms associated with the State Environmental Quality Review Act.
2. Field work will be subject to NYS prevailing wage and supplemental benefits.
3. Field survey services will be completed prior to an accumulation of ice and snow or following complete spring melt. No survey services will occur with snow on the ground.

TASKS NOT INCLUDED IN THIS PROPOSAL

The following efforts are excluded from this scope of services:

1. Cultural / archeological investigations.
2. Boundary survey and/or preparation of easements.
3. Stormwater pollution prevention plan (SWPPP).
4. Wetland or shoreline permit services beyond what is described in Task 01 and Task 02-C.
5. SEQRA services.
6. Design of building and site structures including the proposed comfort station and pavilion beyond building programming.
7. Bid or construction phase services.
8. Public hearings or presentations.
9. 3-dimensional modeling, photo-simulations, or photo-realistic perspective renderings.
10. Viewshed Analysis.
11. Traffic Study.

SCHEDULE

Upon notice to proceed, MJ is prepared to develop a mutually agreeable project schedule that meets critical milestones and begin the project.



FEE

MJ proposes to complete the above-listed services for the following fees.

Description	Lump Sum Fee
Task 1 – Field Investigations	\$ 40,000
Task 2 – Design & Permitting Phase	\$ 79,000
Task 3 – SWPPP	\$ 6,000
Total Fee	\$ 125,000

The fee assumes there are no significant changes resulting from decisions, conditions and/or events beyond MJ's control.

SUMMARY

Thank you for the opportunity to provide a proposal for this project. If the above scope of work is acceptable, please notify MJ and we will provide you with a formal contract for review and execution. We look forward to the opportunity to work with the Village on this project. Please do not hesitate to contact Josiah Simpson at 518-371-0799 ext. 419 or via email at jsimpson@mjteam.com if you have questions or require additional information.

Sincerely,

Michael D. Panichelli, P.E.
President



Figure 1 – Project Limits

